

QUOTATION NOTICE**Quotation Notice No 33 / G-I BDO/WBLAE2021****Dated : 23/02/2021**

Sealed rate quotations are hereby invited from the resourceful bonafied & experienced contractor / supplier for Polling Station repair within Garhbeta-I Dev. Block jurisdiction as per attached Annexure-A, Annexure-B, Annexure-C, Annexure-D & Annexure-E for smooth conduction of General West Bengal Legislative Election 2021. The intending quotationers should be applied their rate inclusive of carriage and all Government duties in prescribed format in word and figures against each item and each annexures to this office on and before **26.02.2021 upto 2.00 P.M.** The quotation will be opened on **01.03.2021 at 11.00 A.M** at the office of the undersigned. The participants of the quotationer will remain present at that time. The work order will be issued to the accepted lowest quotationer and payment of bills will be done as per lowest accepted rate. The undersigned preserves the right of rejection or acceptance of any quotation without assigning any cause of such rejection or acceptance.

The details of the quotations are –

Sl. No.	Name of the GP	Annexure	Remarks
1	For all Polling Stations of Katrauttarbil & Sandhipur GP	A, B, C, D & E	Work order will be issued for that work which will be needed (Polling Station name and number will also be mention)
2	For all Polling Stations of Baramura & Shyamnagar GP		
3	For all Polling Stations of Dhadika & Agra GP		
4	For all Polling Stations of Benachapra & Amkopa GP		
5	For all Polling Stations of Amlagora & Garhbeta GP		
6	For all Polling Stations of Garanga & Kharkusma GP		

Other terms and condition should be followed according to the Govt. norms.


Block Development Officer
Garhbeta-I Dev. Block
&
Assistant Returning Officer
233-Garbata AC

Office of the Block Development Officer
Garhbeta-I Development Block

Memo No.....**441(8)**.....

Dated.....**23/02/2021**.....

Copy forwarded for information to :-


1. The District Magistrate, Paschim Medinipur
2. The Sub-Divisional Officer, Paschim Medinipur
3. DPLO, Paschim Meidnipur and RO, 233-Garbata AC
4. OC, Infrastructure Cell, Paschim Mednipur
5. J.E. (RWP/RWS/BP/AI) Garhbeta - I Dev. Block
6. OC, Election Cell, Garhbeta-I Dev. Block
7. Head Clerk of this Office.
8. Office Notice Board.


Block Development Officer
Garhbeta-I Dev. Block
&
Assistant Returning Officer
233-Garbata AC

ANNEXURE-A

**REPAIRE OF DRINKING WATER SOURCE AT DIFFERENT POLLING STATIONS WITHIN THE
JURISDICTION OF GARHBETA-I DEV. BLOCK**

Sl.No.	Description of items	Tentative quantity	unit	Rate	Amount
1	Repaire of Sub-mersible pump/motor(1HP) including taking out and lowering all complete.	2	No.		
2	Supply, fitting and fixing of PVC schedule 80 medium duty column pipe 32 mm dia.	12.00	Mtrs.		
3	Supply, fitting, fixing of starter with panel board.	2	No.		
4	1.5 sq-mm Finolex or similer brand flat cable	100.00	Mtrs.		
5	Supply, fitting and laying of PVC schedule 80 pipe including subsidiary work all complete (A) For underground work .	30.00	Mtrs.		
6	(B) For Exposed work	35.00	Mtrs.		
7	Washing and development of tubewell with compressor for 8 hrs.	3	Item		
8	Supply, fitting and fixing in position Polythene bib cock incl. Allied materials all complete.	15.00	No.		
9	Construction of stand post including concrete platform.(3'x4')	2.00	No.		
10	Cleaning and disinfection of existing water tank.	3.00	No.		


Block Development Officer
Garhbeta-I Dev. Block
Garhbeta :: Paschim Medinipur

ANNEXURE-B
REPAIRE OF RAMP WITH HANDLE AT DIFFERENT POLLING STATIONS WITHIN THE JURISDICTION OF
GARHBETA-I DEV. BLOCK


Sl.No.	Description of items	Tentative quantity	unit	Rate	Amount
1	1 st class brick work 250 mm thick with sand cement mortar(1:6)	3.50	Cum.		
2	Sand filling including supply of fine sand	4.00	Cum.		
3	Ordinary cement concrete(1:1.5:3)	2.50	Cum.		
4	Supply, fitting and fixing in position railing 750 mm. High with 40 mm dia iron pipe including priming and painting of the same.	200.00	Kg.		
5	Hire and labour charges of shuttering	2.50	Sqm.		
6	15 mm thick plastering (1:6)	10.00	Sqm.		
7	Neat cement punning	10.00	Sqm.		


Block Development Officer
Garhbeta-I Dev. Block
Garhbeta :: Paschim Medinipur

ANNEXURE-C


**REPAIRE OF TOILET AT DIFFERENT POLLING STATIONS WITHIN THE JURISDICTION OF GARHBETA-I
DEV. BLOCK**

Sl.No.	Description of items	Tentative quantity	unit	Rate	Amount
1	Dismantling of AFS flooring	10.50	Sqm.		
2	35 mm thick AFS flooring including neat cementing and skirting al complete.	10.50	Sqm.		
3	Worn out plaster renewing the same with sand cement mortar(1:4)	14.50	Sqm.		
4	Decorative cement based paint as per manufacture's specification	50.00	Sqm.		
5	Supply ,fitting and fixing of Indian type Water Closet with P or S trap	3	Nos.		
6	Supply, fitting and fixing of 150mm dia. PVC soil pipe including necessary fittings all complete.	12.00	mtrs.		
7	Neat cement punning	10.00	Sqm.		
8	Repaire of door and ventilator shutter and frame incl. Colouring the same .	4.00	Sqm.		
9	Supply, fitting and fixing of 15 mm dia PVC Pipe with necessary fittings in position all complete.	12.00	Mtrs.		
10	Supply, fitting ,fixing in position PVC Bib cock	7	No.		


Block Development Officer
Garhbeta-I Dev. Block
Garhbeta :: Paschim Medinipur

ANNEXURE-D
ELECTRIFICATION WORK AT DIFFERENT POLLING STATIONS WITHIN THE JURISDICTION OF
GARHBETA-I DEV. BLOCK

Sl.No.	Description of items	Tentative quantity	unit	Rate	Amount
1	Supply, fitting and fixing 5 amp. 3 pin plug socket including 4"x4" fibre board and switch.	6	Nos.		
2	Casing wiring including supply of 1.5-2.5mm cable and casing.	20.00	Mtrs.		
3	Supply, fitting and fixing of 4'x4" board with bulb holder .	10	Nos.		
4	Swith board (fibre make) with 7nos. Switch and 4 nos. Plug point of size 10"x8" .	2	Nos.		
5	Supply, fitting fixing of self for placing mobile phone during charging.	4	Nos.		
6	Hire and labour charges of ceiling fan for 2 days	8	Nos.		


Block Development Officer
Garhbeta-I Dev. Block
Garhbeta :: Paschim Medinipur

ANNEXURE-E

**REPAIRE OF BOULDER MOORUM ROAD AT DIFFERENT POLLING STATIONS WITHIN THE
JURISDICTION OF GARHBETA-I DEV. BLOCK**

Sl.No.	Description of items	Tentative quantity	unit	Rate	Amount
1	Repaire of road with boulder and moorum including supplying and laying in position with proper compaction.	15.00	Cum.		


**Block Development Officer
Garhbeta-I Dev. Block
Garhbeta :: Paschim Medinipur**